

Step 1:  
Place Indicators in Squares on Walls

Step 2:  
Turn Remote unit on by plugging in the outlet

Step 3:  
Turn Main Unit on in Dirty Room

Step 4:  
Turn each aeration unit on in Dirty Room

Step 5:  
Push Red Button on Remote Unit

Step 6:  
Hold Green Button down to get the room  
deminision set at 97 m3

Step 7:  
Hit Red Button to lock in room at 97 m3

Step 8:  
Go to Dirty Room Check for Green lights on all WiFi indicators  
and Green Ring is on main unit

Step 9:  
Close Door, LOCK door, and  
Seal door with two layers of tape all the way around top  
bottom and both sides

Step 10:  
Hold GREEN button down and press until it counts down from  
3- 2- 1

Step 11:  
Wait for computer remote to calibrate  
(remote will count up aproximately 3-5 minutes then start to  
count down)

Step 12:  
When counter on remote swithces and starts to count down  
take hand held and  
check air quality around the door  
(check door on all sides, top and bottom and four corners for  
leakage of H2O2)

Air Quality hand  
held reading should  
be less than 1 PPM  
to enter room

Step 13:  
Check the door for leaks at 30 minutes into the cycle using hand  
held air quality device

Step 14:  
When Cycle is complete and lights change to Green the Red  
Button will flash Green  
Push the flashing red button to end the cycle.

Step 15:  
Check the air quality around the door seal again with the hand  
held device and record the air quality around the door on the  
log sheet

Step 16:  
NEXT DAY  
Remove tape around door, UNLOCK door, take hand held air quality tester and stick  
arm in the room with door cracked and record air quality at PPM on log sheet